

MAGNUM
DURA-CLAMP
CIRCA FLEX
MODULAR
AL-SPEED

UNISPAN 
Forming & Shoring Solutions

DURA-CLAMP



MODULAR FORMWORK • INSTRUCTION MANUAL

PILOSIO
BUILT TO BUILD

PILOSIO: YOUR QUALITY PARTNER SINCE 1961:

Pilosio SpA designs and produces formworks for walls and slabs, trench lining systems and scaffolds either for sale or rental. With an experience of 50 years, Pilosio brand is synonymous of its elevated quality, pre and post sale service, worldwide distribution net and wide range of products (for the last 50 years, Pilosio brand was – and still – famous for its elevated quality, pre and post sale service, worldwide distribution net and wide range of products.) Our technical office is always at the disposal of our clients to design special solutions in order to resolve the most various requirements of the construction sites we have a special unit of carpentry capable to realize any single pieces upon request. Pilosio equipments are used in the most various fields such as: formworks for walls, slabs and columns, trench lining systems for any type of excavation, scaffolds for construction, maintenance and restoration, theater boxes tribunes and covers for the show business.



Index


<u>4</u>	<u>Components and fittings</u>	<u>47</u>	<u>Lift shaft setting up</u>
<u>22</u>	<u>Reference regulations and rules</u>	<u>49</u>	<u>Working platform for lift shaft</u>
<u>30</u>	<u>Formwork assembly</u>	<u>50</u>	<u>Fittings for formwork</u>
<u>35</u>	<u>Infill bar and panel</u>	<u>60</u>	<u>Climbing supporting bracket</u>
<u>37</u>	<u>Making corners</u>	<u>62</u>	<u>Examples of special applications</u>
<u>41</u>	<u>Making corners and "T" junction</u>	<u>66</u>	<u>Replacement and maintenance of alkus panel</u>
<u>42</u>	<u>Continuation of existing walls</u>	<u>70</u>	<u>Cleaning of the formwork "DURA-CLAMP"</u>
<u>43</u>	<u>Columns setting up with adjustable panel</u>	<u>71</u>	<u>"DURA-CLAMP" form work class</u>
<u>45</u>	<u>Columns setting up with panel</u>	<u>72</u>	<u>Project data</u>
<u>46</u>	<u>Example of inclined walls setting up</u>		

Components and fittings

Name	Dimensions	Weight	Weight	Code
	LxH (in.)	lbs	kg	


DURA-CLAMP PANEL H=8'-0"

LxH (in.)	lbs	kg	
2' x 8'	113.8	51.6	5202561ZPK
1' 6" x 8'	95.9	43.5	5202545ZPK
1' x 8'	76.5	34.7	5202530ZPK
6" x 8'	56.2	25.5	5202515ZPK




Adjustable Panel (for columns and corners)

LxH (in.)	lbs	kg	
3' x 8'	94.6	42.9	5202591FZPK
3' x 4'	48.5	22.0	5201291FZPK
3' x 2'	25.1	11.4	5200691FZPK




DURA-CLAMP PANEL H=2'-0"

LxH (in.)	lbs	kg	
2' x 4'	61.7	28.0	5201361ZPK
1' 6" x 4'	53.8	24.4	5201345ZPK
1' x 4'	43.0	19.5	5201330ZPK
6" x 4'	29.5	13.4	5201315ZPK




DURA- CLAMP

Name	Dimensions	Weight	Weight	Code
	LxH (in.)	lbs	kg	




DURA-CLAMP PANEL

H=2'-0"	LxH (in.)	lbs	kg	
	2' x 2'	35.1	15.9	5200661ZPK
	1' 6" x 2'	30.4	13.8	5200645ZPK
	1' x 2'	23.6	10.7	5200630ZPK
	6" x 2'	15.4	7.0	5200615ZPK



Inner corner (8" + 8")	LxH (in.)	lbs	kg	
	8'	98.5	44.7	5232440ZP
	4'	52.0	23.6	5231240ZP
	2'	40.3	18.3	5230640ZP




Inner corner (4" 23/32" + 4" 23/32")	LxH (in.)	lbs	kg	
Complete with: N. 8 Washer 25/32"x 2"1/8" UNI 6593 N. 8 Screw M18x50 UNI 5737 N. 8 Nut M18 UNI 5588	8'	75.4	34.2	5232420
Complete with: N. 4 Washer 25/32"x 2"1/8" UNI 6593 N. 4 Screw M18x50 UNI 5737 N. 4 Nut M18 UNI 5588	4' 2'	37.5 21.2	17.0 9.6	5241240 5240640


Components and fittings

Name	Dimensions	Weight	Weight	Code
	LxH (in.)	lbs	kg	


Outer corner (0" + 0")	LxH (in.)	lbs	kg	
	8'	57.3	26.0	5232400ZP
	4'	29.8	13.5	5231200ZP
	2'	15.2	6.9	5230600ZP




Outer corner with hinge (8" + 8")	LxH (in.)	lbs	kg	
	8'	141.1	64.0	5232454ZP
	4'	73.6	33.4	5231254ZP
	2'	37.5	17.0	5230654ZP



Inner corner with hinge (8" + 8")	LxH (in.)	lbs	kg	
	8'	133.4	60.5	5232444ZP
	4'	68.3	31.0	5231244ZP
	2'	35.5	16.1	5230644ZP




DURA- CLAMP




Name	Dimensions	Weight	Weight	Code
	LxH (in.)	lbs	kg	

Infill bar	LxH (in.)	lbs	kg	
H=8'	1" x 8'	20.9	9.5	5242402ZP
	2" x 8'	30.0	13.6	5242405ZP
	3" x 8'	58.2	26.4	5242407ZP
H=4'	1" x 4'	11.2	5.1	5241202ZP
	2" x 4'	16.3	7.4	5241205ZP
	3" x 4'	30.0	13.6	5241207ZP
H=2'	1" x 2'	6.4	2.9	5240602ZP
	2" x 2'	9.0	4.1	5240605ZP
	3" x 2'	16.5	7.5	5240607ZP



Infill Panel	LxH (in.)	lbs	kg	
	8'	93.5	42.4	5242440
	4'	47.4	21.5	
	2'	24.5	11.1	




Conical corner (12" x 12")

	LxH (in.)	lbs	kg	K5233244ZP
Complete with: N. 8 Plate 3" 29/32" x 3" 1/8" x 3/8" for tierod N. 8 Screw M18x100 UNI 5739 Zn N. 8 Nut M18 UNI 5588 Zn N. 8 Washer 25/32" x 2" 1/8" UNI 6593 Zn	8'	303.1	137.5	582930 15V1860TZ 15D18NZ 15R18GZ
(15" x 15")	LxH (in.)	lbs	kg	K5233366ZP
Complete with: N. 16 Plate 3" 29/32" x 3" 1/8" x 3/8" for tierod N. 16 Screw M18x100 UNI 5739 Zn N. 16 Nut M18 UNI 5588 Zn N. 32 Washer 25/32" x 2" 1/8" UNI 6593 Zn	1'	519.2	235.5	582930 15V1860TZ 15D18NZ 15R18GZ


Components and fittings

Name	Weight	Weight	Code
	lbs	kg	


Aligning connector	lbs	kg	
	5.3	2.4	5260000




Adjustable connector	lbs	kg	
	6.6	3	5260050




Connector for alignment	lbs	kg	
	10.1	4.6	5260010



Alignment connector for horizontal setting up	lbs	kg	
N. 1 waler plate D15	15.7	7.1	526070




DURA- CLAMP




Reinforcement "U" channel	lbs	kg	
	7.7	3.5	554042




Threaded bar (D15)	LxH (in.)	lbs	kg	
	9" 27/32"	0.8	0.37	583025
	1' 7" 11/16"	1.6	0.73	583050
	2' 5" 17/32"	2.3	1.05	583075
	3' 3" 3/8"	3.1	1.42	583100
	4' 11" 1/16"	4.9	2.20	583150
	6' 6" 3/4"	6.4	2.90	583200




D15 swivel plate	lbs	kg	
	2.6	1.2	583905



D15 waler plate	lbs	kg	
	2.6	1.2	583900



D15 nut with wings	lbs	kg	
	0.7	0.34	583907




D15 nut	lbs	kg	
	0.24	0.11	583910
Washer	lbs	kg	
	0.04	0.02	15R18GZ


Components and fittings

Name	Dimensions	Weight	Weight	Code
	LxH (in.)	lbs	kg	


Plate for tie-rod	LxH (in.)	lbs	kg	
	L= 3" 29/32" H= 3" 1/8" S= 3/8"	1.3	0.6	582930




Mobile tie-rod retainer	lbs	kg	
	5.7	2.6	5270021




Tie-rod for connection of columns	lbs	kg	
	2.2	1	5250005




Connecting device for outer corners	lbs	kg	
	2.9	1.3	5250010



Reinforcement crossbar	lbs	kg	
	18.7	8.5	556080



DURA- CLAMP




Name	Weight	Weight	Code
	lbs	kg	


Pin P300	lbs	kg	
	0.7	0.33	581010




Wedge	lbs	kg	
	0.33	0.15	581100




Water stop D15	lbs	kg	
	1.5	0.7	583940



Cotter pin Ø 7/64"	lbs	kg	
	0.018	0.008	15COP3



PVC Plug Ø 15/16"	lbs	kg	
	0.002	0.001	584024



PVC Spacer Øi 27/32" da 2000	lbs	kg	
	0.7	0.3	584201




PVC Plastic cone Øe 27/32"	lbs	kg	
	0.004	0.002	584101

Components and fittings

Name	Weight	Weight	Code
	lbs	kg	


Working bracket with adjustable support for metallic boards

Complete with: N. 1 Cotter Pin Ø 7/64"	24.7	11.2	K591005
---	------	------	---------




Guardrail frame

Complete with: N. 1 Cotter Pin Ø 7/64"	16.1	7.32	591025
---	------	------	--------




Climbing support bracket of 7' 10" 62/127"

Complete with:	lbs	kg	K593100
N. 1 Bracket of 7' 10" 15/32" (A)	176.4	80.0	
N. 1 Guardrail post of 7' 10" 15/32" (B)	19.4	8.8	
N. 1 Lower stage standard of 9' 10" 3/32" (C)	97.7	44.3	
N. 1 Lower stage tube of 11' 5" 25/32" (D)	30.2	13.7	
N. 1 Lower stage crosspiece of 3' 11" 7/32" (E)	34.6	15.7	
N. 1 Sliding trolley of 4' 5" 17/32" (F)	70.5	32.0	
N. 1 Guide covering of 2' 11" 13/32" (G)	10.4	4.7	
N. 1 Panel support (H)	17.2	7.8	
N. 1 Push pull prop 6' 2" 25/32" (I)	55.1	25.0	
N. 1 Anti lifting device with D15 bar (L)	4.2	1.9	




DURA- CLAMP



Name	Dimensions	Weight	Weight	Code
	LxH (in.)	lbs	kg	


Support bracket	lbs	kg	
Complete with: N. 1 Guardrail post L= 4' 11" 1/32" N. 1 Anti lift device support N. 1 Cotter pin Ø 7/64" N. 1 Tie rod L. 2' 5" 1/2" with welded nut N. 1 Wing nut D15 N. 1 Screw M12x80 UNI 5737 Zn N. 1 Nut M12 UNI 5588 Zn N. 1 Washer 1/2"x15/16" UNI 6592 Zn (Connecting tubes are excluded)	97.0	44.0	592000
Lower stage for supporting bracket	lbs	kg	
Complete with: N. 1 Tube Ø48 L= 10' 10" 11/16" end drilled N. 1 Tube Ø48 L= 7' 2" 7/32" end drilled N. 8 Screw M12x80 UNI 5737 Zn N. 8 Nut M12 UNI 5588 Zn N. 8 Washer 1/2"x15/16" UNI 6592 Zn (Connecting tubes are excluded)	103.6	47.0	



Mobile adjustable platform	LxH (in.)	lbs	kg	
Complete with: N. 1 Mobile adjustable platform (A) N. 8 P300 pin (B) N. 12 Cotter pin Ø 7/64" (C) N. 4 Tube Ø1" 7/8"x1/8" (D) N. 4 P300 pin (E) N. 2 Beams for the lower platform (F)	4' 9" 1/16" - 7' 8" 1/2"	196.2	89.0	K598300
	7' 10" 15/32" - 9' 10" 3/32"	264.6	120.0	K598310


Components and fittings

Name	Dimensions	Weight	Weight	Code
	LxH (in.)	lbs	kg	



Mobile coupling for working platform

598200



Supporting and shoring bracket

lbs

kg

833.3

378


593050

DURA- CLAMP


Name	Dimensions	Weight	Weight	Code
	LxH (in.)	lbs	kg	



Bracket fixing device with nut	lbs	kg	
Complete with: N. 1 D15 Nut N. 1 Washer for tie-rod	17.6	8.0	592020




M24 tie-rod for bracket fixing device	lbs	kg	
Complete with: N. 1 Nut M24 UNI 5587 Zn N. 1 Plate (3" 29/32" x 3" 29/32" x 3/8") with D25 hole	17.6	8.0	592030



Adjustable supporting anchor	lbs	kg	
Complete with: N. 1 D15 Nut N. 1 Washer for tie-rod N. 1 Screw M14x80 UNI 5739 Zn	23.1	10.5	598000


Components and fittings

Name	Dimensions	Weight	Weight	Code
	LxH (in.)	lbs	kg	



Push-pull prop	LxH (in.)	lbs	kg	
Complete with:	5' - 8'	32.2	14.6	591100
N. 1 Tilt plate	7' - 12'	46.3	21.0	591200
N. 1 Connector for push-pull prop	10' - 15'	55.1	25.0	591201
N. 1 P300 pin	17' - 23'	127.9	58.0	591300
N. 1 Cotter pin Ø 7/64"				
N. 1 Screw M20x100 UNI 5737 Zn				
N. 2 Self locking nut M20 UNI 7473 Zn				

DURA- CLAMP



Adjustable Arm


Complete with:
 N. 1 Connector for push pull prop
 N. 2 P300 pin
 N. 2 cotter pin $\varnothing 7/64''$
 N. 1 screw M20x100 UNI 5737 Zn
 N. 1 self locking nut M20 UNI 7473 Zn

LxH (in.)

lbs

kg

591102



Fixed Arm


Complete with:
 (for push pull prop 591200 and 591201)
 N. 1 Connector for push-pull prop
 N. 2 P300 pin
 N. 2 cotter pin $\varnothing 7/64''$
 N. 1 screw M20x100 UNI 5737 Zn
 N. 1 self locking nut M20 UNI 7473 Zn

LxH (in.)

lbs

kg

591210



Adjustable Arm


Complete with:
 (for push pull prop 591200 and 591201)
 N. 1 Connector for push-pull prop
 N. 2 P300 pin
 N. 2 cotter pin $\varnothing 7/64''$
 N. 1 screw M20x100 UNI 5737 Zn
 N. 1 self locking nut M20 UNI 7473 Zn

LxH (in.)

lbs

kg

591205



Adjustable Arm

Complete with:
 (for push pull prop 591300 and 591310)
 N. 1 Connector for push pull prop
 N. 2 P300 pin
 N. 2 cotter pin $\varnothing 7/64''$
 N. 1 screw M20x100 UNI 5737 Zn
 N. 1 self locking nut M20 UNI 7473 Zn

LxH (in.)

lbs

kg

591305

Accessories for push-pull prop

A) Connector for push-pull prop
 B) Tilt plate $45/64'' \times 5/8''$
 C) P300 pin
 D) Cotter pin $\varnothing 7/64''$
 E) Screw M20x100 UNI 5737 Zn
 F) Self locking nut M20 UNI 7473 Zn

lbs


kg

2059P825
 2059P829
 581010
 15COP3
 15V20100PZ
 15D20FZ


Components and fittings

Name	Dim.	Weight	Weight	Code
	LxH (in.)	lbs	kg	


Counter beam TL 250	lbs	kg	
Complete with: N. 1 Strut L= 7' 6" 17/32" N. 3 Screw M20x100 UNI 5737 Zn N. 3 Nut M20 UNI 5588 Zn N. 2 D15 wing nut	363.8	165.0	K594250




Accessories for counter beam	lbs	kg	
A) Connection tie-rod	1.32	0.60	594410
B) Swivel plate D15	2.6	1.20	583900
C) Cotter pin Ø 7/64"			15COP3
D) Washer 25/32"x 2" 1/8" UNI 6593 Zn	0.04	0.02	15R18GZ
E) P300 pin	0.7	0.33	581010
F) Panel support MINIMAG Imperial	12	5.40	594430
G) D15 Nut	0.2	0.11	583910



Anchor	LxH (in.)	lbs	kg	
Complete with:				
N. 1 Water Plate D20		3.3	1.5	585900
N. 1 Disposable Water D20		3.3	1.5	585900
N. 1 Tie-rod	2' 5" 1/2"	4.3	1.95	585075
N. 1 Tie-rod	4' 11" 1/32"	8.6	3.9	585150
N. 1 Pvc spacer	6' 6" 23/32"	0.7	0.3	584210




DURA- CLAMP




Name	Dim.	Weight	Weight	Code
	LxH (in.)	lbs	kg	

TS 150 Counter beam	LxH (in.)	lbs	kg	
Complete with: N. 4 Screw M16x55 UNI 5739 Zn N. 4 Nut M16 UNI 5588 Zn N. 4 Washer 21/32"x1 11/64" UNI 6592	2' 4" 7/8" x 4' 9" 1/32"	140.0	63.5	K594150



TR 300 Counter beam	LxH (in.)	lbs	kg	
	6' 8" 3/32" x 11' 10" 3/32"	782.6	355.0	594301




Longitudinal beams	LxH (in.)	lbs	kg	
	2' 1"- 9/16" 7' 10" 15/32" 9" 9"5/16"	77.2 173.3 214.3	35.0 78.6 97.2	594970 556240 594900


Components and fittings

Name	Dimensions	Weight	Weight	Code
	LxH (in.)	lbs	kg	

Panel container frame	lbs	kg	
Complete with: N.1 Sliding Block N.1 Bend tie-rod N.1 Bush $\varnothing 1" 5/32"$ L= 0' 1" 9/16" N.1 Screw M14x70 UNI 5737 Zn N.1 Nut M14 N.1 Washer UNI 8842 A14 Zn (jagged)	27.3	12.4	437000




Adjustable base	lbs	kg	
	11.9	5.4	557010




Drilling of Alkus Panel (7' 11" 1/2")

	LxH (in.)	lbs	kg	
(On request)	1' 11" 7/16"	36.6	16.6	2052P584
	1' 5" 7/16"	27.3	12.4	2052P585
	0' 11" 7/16"	17.9	8.1	2052P586
	0' 5" 3/8"	8.4	3.8	2052P587
(3' 11" 15/32")	LxH (in.)	lbs	kg	
(On request)	1' 11" 7/16"	18.3	8.3	2052P588
	1' 5" 7/16"	13.4	6.1	2052P589
	0' 11" 7/16"	8.8	4.0	2052P590
	0' 5" 3/8"	4.2	1.9	2052P591
(2' 11" 15/32")	LxH (in.)	lbs	kg	
(On request)	1' 11" 7/16"	13.7	6.2	2052P596
	3' 11" 15/32"	27.6	12.5	2052P597
	7' 11" 1/2"	55.3	25.1	2052P598



DURA- CLAMP



Name	Dim.	Weight	Weight	Code
	LxH (in.)	lbs	kg	



Guide Bush	lbs	kg	
	0.009	0.004	2052PG09



Self drilling screw	LxH (in.)	lbs	kg	
	Ø 27/128"x 1" 45/128"	0.0099	0.0045	07605533



A) Pump for dismantling liquid application (11 l.)

	lbs	kg	
	8.8	4	150ILPOM
B) Dismantling fluid for Pilosio formwork (25 l.)	lbs	kg	
	49.2	22.3	150ILDIS

Reference regulations and rules

INTRODUCTION

In addition to the instructions given below, the following regulations and standards must be complied with:

- EN 15113 "Vertical formwork."
- EN 13374 "Protection guardrails."

Regulations of reference on safety matters

All operational and dimensional references shown in this Manual refer to the regulations in force on Italian territory. For application in other countries, comply with the regulations in force in that country.

GENERAL PROVISIONS

The preparation, assembly, handling, installation and dismantling operations must be carried out by qualified personnel under the supervision of a construction manager who must ensure that:

- the above-mentioned operations are carried out professionally and in absolute safety complying with the instructions and drawings supplied with the formwork;
- the lifting/handling equipment and the relative load-bearing devices to be used for the handling and positioning of the formwork are suitable for the purpose.
- all the members which make up the structures and the equipment are checked thoroughly before use in order to remove those which, due to breakages, deformations or corrosion, do not guarantee total reliability.
- the workers who are to carry out the assembly, handling, installation, checking and dismantling of the structures are in possession of the correct equipment to do so and, depending on the risks involved, use the following individual protective equipment: safety harnesses; gloves; helmets; boots.

The operations for handling the structural members must be planned by the construction site manager in accordance with the installation sequence and the instructions provided by the manufacturer. The operations which require the wearing of safety harnesses must be clearly specified and instructions on the use of harness attachments must be provided. If, during handling operations, it is necessary to remove some guardrails, specific instructions must be provided for the correct operational procedures to be followed by the workers. During the working phases, anchorage systems must be fitted as indicated in the drawings provided with the formwork. These anchorages must guarantee sufficient yield strength during use of the equipment for the stresses transmitted by the formwork. The coupling devices must fix together the members in such a way that they may only be separated by means of a deliberate operation, excluding the possibility of any accidental opening of the devices. A specific design must be prepared by a qualified professional for any deformation which does not fall within the dimensions and/or overloads specified in the operational diagrams, or for the use of provisional equipment. The various configurations and/or major changes, even if needed during progress of the work, must be indicated on the final assembly drawings. An Operational Safety Plan must be prepared by the construction firm, providing details for the handling, assembly, use and dismantling of the equipment.

PRE-ASSEMBLY INSTRUCTIONS

Technical documentation provided with the formwork

The user must receive the following documentation from the manufacturer:

- specific instructions regarding the correct assembly, use and dismantling;
- technical documentation, where necessary, with details of the design parameters and loads;
- assembly drawing with additional and explanatory instructions.

Equipment qualification check

Before assembly it is necessary to check that:

- the metal frame of the formwork is not deformed and that the welding is satisfactory (absence of breakages, cracks, etc.);
- the panel is free from deposits and protected against water absorption;
- the devices provided for setting up the formwork are in full working order (wing nuts, clamps, alignment devices, tie rods etc.);
- the lifting and handling devices are in full working order and correctly maintained (normal and extra-height hooks, lifting pins, equalizers, etc.);
- the working brackets are in full working order and correctly maintained, especially the formwork attachments. The anti-slip decks must be no less than 8" wide and 1" 1/2" thick (boards 8"x 2"), free from mould, cracks and with few through knots (reduction of deck section by less than 10%);
- the props are not deformed (giving particular attention to the formwork attachments, ground anchorages, locking pins) and that the welding is satisfactory.

Formwork storage

The materials may require a large amount of storage space so the area must be carefully chosen to avoid the obstruction of paths and interference with the site roads.

The position of the storage area should also be as close as possible to the place of assembly in order to avoid unnecessary handling of the equipment.

The formwork is stored in special containers in which the panels are placed with the plywood surface facing upwards. Only the top panel will have the plywood facing upside down. For storage directly on the ground, the panel surface should face upwards, to avoid the accumulation of water. Supporting beams are placed on the ground to keep the formwork clean and dry and also allow easy lifting of the formwork for the following working phases.

Lifting and handling

These operations can take place in the storage area or in the working area where slabs/floors are to be prepared, moving formwork from one floor to the other.

Before starting the operations for lifting and moving the formwork from the storage area to the working area it is necessary to lock the formwork together by means of tie rods.

The lifting and handling of the formwork is carried out by using steel cables attached to the crane hook.

It is necessary to check that the actual load on the cables, depending on the weight to be lifted (the dynamic increase must also be taken into account) and the angle of the cable with respect to the formwork, does not exceed the capacity of the cables indicated by the manufacturer.

The lifting and handling operations from one concrete casting phase to another must be carried out with formwork in a vertical position, using a special self-blocking hook or a hook suitable for extra heights. It is once again necessary to check that the actual load on the lifting cables and the loads lifted are less than the respective capacity of the cables and lifting hook. Access to the lifting and handling areas is strictly forbidden.

INSTRUCTIONS FOR ASSEMBLY, USE AND DISMANTLING

In order to assess the main risks present on the construction site due to use of the formwork (as foreseen by the Legislative Decree 494/96), they should be listed by type of activity and situations, and a summary of the measures to be taken should also be provided.

- technical documentation, where necessary, with details of the design parameters and loads;
- assembly drawing with additional and explanatory instructions.

Installation - overturning of formwork

The formwork must be placed in an oblique and/or vertical position whilst awaiting the subsequent reinforcement placing or concrete casting phases. In this position the formwork is isolated and subject to wind loads which can vary from minimum values of 4,1 psf to values of 16,50/20,50 psi, depending on the height and exposure. It is therefore advisable to reduce to the absolute minimum the time that the formwork must be in this position, where it is at the greatest risk when wind speeds exceed 35,80 mph.

Overturning can also be due to other causes, such as an unlevel or unstable support base, or crane operation errors whilst moving buckets, other formwork, reinforcement etc. The aim of the adjustable props is, as well as correctly aligning the formwork, to stabilize the formwork whilst awaiting the casting phase. It is advisable to fix the stirrup of the prop to the ground (with a bar inserted into the ground or an expanding plug in the case of a concrete base), especially in the presence of strong winds and if the formwork is isolated. Alternatively, use could be made of suitable ballast placed on the stirrups.

The number of props must be calculated on the basis of the dimensions of the formwork and the intensity of the wind load, but, in any case, at least two must be fitted.

Installation - falling objects

There is the risk of falling objects during all installation phases, unless a working platform is included.

A worker who checks the wing nuts, alignment devices, pins and wedges etc, or climbs on special ladders or on the formwork itself, if there is the relative frame fixed to it, must use a safety harness with double ropes and spring catch devices.

Use - Collapse of formwork

The concrete pressure acts on the alkus panel surface and on the tie rods which connect together the formwork holding the concrete. The metal frame of the formwork and the tie rods with wing nuts are the components which ensure the safety of the workers, during the concreting phase, who are working on the ground near to the formwork and on the working platforms, which are connected to the formwork frame.

The ends of the tie rods may sometimes be covered with plastic plugs to avoid any contact with the panel uprights.

It is therefore necessary to check that the tie rods – wing nuts are satisfactorily tightened together and that the concrete pressure, which mainly depends on the speed and height of the concrete casting, does not exceed the design pressure for the formwork as specified by the manufacturer (1230 psf). In order to determine the concrete pressure, reference should be made to the diagram of UNI standard U50.00.206.0 "Formwork - safety requirements".

Use - Falling objects

During the concrete casting phase, working brackets and working decks are used with a width of not less than 24" and fitted with a suitable guardrail (1st ledger must be placed at the height of at least 1 m from the working deck, 2nd ledger no more than 24" away from the 1st, toe board at least 8" high), both lengthways and at the ends of the scaffolding.

Any maintenance decks must be at least 24" wide.

Access to the scaffold structures must be by means of a ladder and manhole included on the deck.

Dismantling



The safety measures to be taken with regards to the risks resulting from overturning of the formwork or falling objects are the same as those indicated for the installation.

The person in charge of dismantling must:




- ensure that the formwork is kept stable by the props before unfastening the tie rods. After the self-locking lifting hook has been inserted, the person must move away from the formwork before the lifting phase begins.
- the formwork accessories (wing nuts, alignment devices, bars and tie rods etc.) must be lowered to the ground by suitable equipment, and they must not be merely dropped to the ground.

Formwork assembly

"DURA-CLAMP" PROFILE CHARACTERISTICS




MATERIAL:
EN 10149-2 - S315MC



Panel Connection with "DURA-CLAMP"
Aligning Connector

DURA- CLAMP

Connection with "MAGNUM" Panel




Formwork assembly



DURA-CLAMP ALIGNING CONNECTOR




Panel connection utilizing the "DURA-CLAMP" aligning connector.



Formwork assembly: use timber battens to level supporting surface.



PUSH PULL PROP





WORKING BRACKET

LIFTING HOOK

Formwork assembly: fit accessories (brackets and props) and raise by lifting hooks.


Setting up "DURA-CLAMP" Panels

SETTING UP WALL 1





Wall nr.1: assemble spacers with tie rods and plumb panels using props.

SETTING UP WALL 2




Wall nr.2: repeat previous operation with opposite panels.

Closing formwork: when both panels are positioned, tighten tie rods; parallelism and distances between panels are guaranteed by tie rod with spacers.







TIGHTENING OF TIE ROD

Formwork assembly



Infill bar and panel

DURA-CLAMP



Infill bar and panel "NOT AVAILABLE IN USA"

D15 TIE-ROD LG=1' 7" 21/32"

WASHER FOR TIE-ROD




INFILL PANEL

PANEL "MINIMAG IMPERIAL"

NUT D15

SWIVEL PLATE D15




REINFORCING "U" CHANNEL






Making corners

DURA-CLAMP




Alternative systems for making corners



Making corners with column panels














ADJUSTABLE PANEL
FOR COLUMNS AND CORNERS



Making corners



Marking corners with outer corner



Making corners

DURA-CLAMP

Corner junctions: solution with variable opening corners




THE TABLE SHOWS THE CORRECT WIDTH Y OF THE OUTER INFILL BAR TO BE USED DEPENDING ON THE SIZE OF THE CORNER TO BE CREATED A AND THE THICKNESS OF THE WALL S

A S	75°	90°	120°	135°	150°	Y
8"	10" 21/32"	8"	4" 1/4"	2" 13/16"	1" 17/32"	
10"	1' 1" 9/32"	10"	5" 13/32"	3" 21/32"	2" 1/16"	
12"	1' 3" 7/8"	1'	6" 9/16"	4" 15/32"	2" 19/32"	
1'2"	1' 6" 1/2"	1' 2"	7" 23/32"	5" 5/16"	3" 1/8"	
1'4"	1' 9" 3/32"	1' 4"	8" 7/8"	6" 1/8"	3" 21/32"	
1'6"	1' 11" 23/32"	1' 6"	10" 1/32"	6" 31/32"	4" 3/16"	
1'8"	2' 2" 5/16"	1' 8"	11" 3/16"	7" 25/32"	4" 3/4"	
1'10"	2' 4" 29/32"	1' 10"	1' 11/32"	8" 5/8"	5" 9/32"	







Making "T" junctions

Use outer and inner corners for making corners and "T" junctions




Continuation of existing walls

DURA-CLAMP




Columns setting up with adjustable panel



HOLES NOT NEEDED ARE CLOSED WITH PVC PLUGS

SWIVEL PLATE D15





TIE ROD FOR COLUMN CONNECTION

X	Y
8"	11"
10"	13"
12"	15"
14"	17"
16"	19"
18"	21"
20"	23"
22"	25"
24"	27"
26"	29"
28"	31"
30"	33"

PUSH-PULL PROP

ADJUSTABLE ARM



DURA- CLAMP

INFILL BAR



OUTER CORNER 0" + 0"

2"



1' 6"

1' 6"



CONTAINMENT DEVICE



COMPENSATION



Example of inclined walls setting up




Lift shaft setting up

DURA-CLAMP

EXAMPLE WITH OTHER CORNER 0" + 0"
AND ADJUSTABLE PANEL


Example with infill panel



2nd Solution - Corner made with outer
corner panel of 0" + 0"

1st Solution - Corner made with
adjustable panel

TIE ROD LG=1' 7" 21/32"
WITH D15 NUT AND PLATE




Lift shaft setting up

SCREW M18x100 UNI 5739,
WASHER 25/32"x 2" 1/8" UNI 6593
NUT M18 UNI 5588

PLATE 3"29/32"x3"1/8"x3/8"


DISARM GIVING A VERTICAL
AND UNIFORM PULL ON ALL
THE STRIPPING CORNERS

Example with corner stripping




Working platform for lift shaft

DURA-CLAMP




Fittings for formwork

1st Solution - Working bracket with wooden boards




2nd Solution - Working bracket with metal boards




DURA-CLAMP

Adjustable props: used to stabilise the formwork




Fittings for formwork




DURA-CLAMP


Lifting hook



Fittings for formwork




PVC PLASTIC CONE Art. 584101




PLUG D24 Art. 584024

PVC SPACER Art. 584201




WATER STOP D15 Art. 583940

Assembly of tie rod and plastic fittings




DURA-CLAMP




STACKING POSSIBLE FOR FORMWORK
WITH WIDTH $\leq 3' 11" 7/32"$

Panels container frame




Fittings for formwork

Adjustable supporting anchor




DURA-CLAMP



Alignment connector for horizontal setting up

D15 SWIVEL PLATE




FOUNDATION PLINTH SOLUTION

ALIGNMENT CONNECTOR
FOR HORIZONTAL SETTING UP


WOODEN BATTEN FIXED TO GROUND

WOODEN BATTEN FIXED TO GROUND

Fittings for formwork




Mobile tie passage




D15 NUT

PLATE FOR TIE-ROD 3" 29/32"x 3"1/8"x 3/8"

DURA-CLAMP




Climbing supporting bracket




These drawings are only intended as guidelines and are not binding for constructional purposes. Reference should be made to the technical documentation provided with the equipment for details on installation, use and dismantling. Contact our technical department if the technical documentation is missing.

DURA- CLAMP

Phase 1: Casting




Phase 2: Slab casting




M24 TIE-ROD WITH WELDED NUT

PLASTIC TUBE Ø1"5/32" TO BE FITTED FOR THE TIE-ROD TO FIX THE SUPPORTING BRACKET


PLATE
3"29/32"x 3"29/32"x3"29/32"



Phase 3: Resumption with bracket then next cast



Phase 4: Resumption with bracket for lower platform and cast



These drawings are only intended as guidelines and are not binding for constructional purposes. Reference should be made to the technical documentation provided with the equipment for details on installation, use and dismantling. Contact our technical department if the technical documentation is missing.

**Shoring beam TL250
for formwork
H max. 10"**




Fixing to the base with tie-bar

D20 Water Plate

DURA-CLAMP


Shoring beam TR300
for formwork
H max. 10"



These drawings are only intended as guidelines and are not binding for constructional purposes. Reference should be made to the technical documentation provided with the equipment for details on installation, use and dismantling. Contact our technical department if the technical documentation is missing.

Examples of special applications


Shoring beam for formwork H 15'



These drawings are only intended as guidelines and are not binding for constructional purposes. Reference should be made to the technical documentation provided with the equipment for details on installation, use and dismantling. Contact our technical department if the technical documentation is missing.



DURA-CLAMP

FIRST SOLUTION



Shoring beam anchor detail

SECOND SOLUTION




L = LENGTH TO BE DEFINED BY THE CUSTOMER ACCORDING TO THE LOAD INDICATED AND THE REINFORCED CONCRETE CHARACTERISTICS

D15 SWIVEL PLATE (CODE 583905) CAN BE USED FOR (X) UP TO 120 kN

D20 WALER PLATE (CODE 583900) MUST BE USED FOR (X) UP TO 220 kN

Replacement and maintenance of alkus panel


Main features of alkus panel




	ALKUS
THICKNESS	9/16"
WEIGHT	12.8 kg/m ²
MODULE OF ELASTICITY (3-POINTS) LONGITUDINAL E 21° C (N/mm ²) DIAGONAL	2500 1700
SIDE EDGES	PROTECTED WITH PAINT
MOISTURE ABSORPTION (WHOLE PANEL)	NONE
NAIL HOLDING ABILITY	COMPARABLE WITH PLYWOOD SHEETS COATED WITH PHENOLIC RESIN
SCRATCH RESISTANCE (N)	0.7
NUMBER OF RE-USES	100 EACH SIDE
DISMANTLING SOLUTION	INDISPENSABLE
THERMAL CONDUCTIVITY	0.12 W/mK

DURA- CLAMP


Alkus panel surface replacement




REMOVE THE SCREWS



REMOVE THE USED COUNTER-CASTING PANEL



SECURE THE ALKUS PANEL
WITH THE SCREWS PROVIDED



INSERT THE NEW ALKUS PANEL POSITIONING THE PVC
GUIDE BUSH INTO THE PREVIOUSLY PREPARED HOLES

Replacement and maintenance of alkus panel

MAINTENANCE INSTRUCTIONS

In addition to the usual maintenance works, consisting of cleaning the formwork and the various fittings and application of dismantling fluid on the counter-casting surface of the alkus, the following instructions must be followed to ensure full maintenance of the frame, brackets and push-pull props.

Small damages, stains peeling etc. of the metallic frame of the formwork, the working brackets and the push-pull props can be repaired with the usual methods. If the damage seems more serious then it is advisable to substitute the parts.


Lifting Accessories

Hooks, lifting pins and equalizers must be replaced even if they are only slightly damaged.

Alkus panel


Minor damage to the alkus, such as holes etc, may be filled. For better results, repair kits are available on the market consisting of alkus disks which are glued to a hole made in the damaged part by using a special tool. If the alkus board is more seriously damaged, or shows signs of swelling due to water absorption, etc, it is advisable to fit a new alkus board.

DURA- CLAMP




Position of fixing screws on alkus panel

PANELS	BUSH	SCREW
PANELS H=8'	4	18
PANELS H=4'	4	10
PANELS H=2'	4	6




Cleaning of the formwork "MINIMAG IMPERIAL"

We recommend cleaning the formwork before each concrete casting in order to keep it in good working order




1st AFTER THE CONCRETE CASTING,
IF NECESSARY, USE WATER TO REMOVE
ANY CONCRETE REMAINING ON THE
OUTSIDE OF THE FORMWORK.



2nd IMMEDIATELY AFTER DISMANTLING THE
PANELS OR BEFORE THE NEXT CASTING,
REMOVE ANY CONCRETE WITH A SCRAPER
AND APPLY A THIN LAYER OF DISMANTLING
FLUID OVER THE ENTIRE SURFACE.


BRUSH AND SCRAPER →



Project data

DURA- CLAMP

Max. allowable concrete pressure on formwork (Rodin)

R (m/h)	Hm (m) in funzione di t e R					Hm (m)	Pm (daN/m ²)	
	25°C	20°C	15°C	10°C	5°C		CN	CV
0.50	1.22	1.34	1.50	1.68	2.02	1.25	2150	2950
1.00	1.55	1.70	1.90	2.15	2.60	1.30	2250	3100
1.50	1.80	2.00	2.25	2.50	3.00	1.35	2325	3225
2.00	2.00	2.20	2.45	2.75	3.35	1.40	2400	3350
2.50	2.15	2.40	2.70	3.05	3.65	1.45	2475	3450
3.00	2.35	2.55	2.85	3.25	3.90	1.50	2575	3550
3.50	2.45	2.70	3.05	3.45	4.15	1.55	2675	3675
4.00	2.55	2.85	3.15	3.60	4.30	1.60	2750	3800
4.50	2.70	2.95	3.30	3.75	4.50	1.65	2850	3925
5.00	2.80	3.10	3.45	3.90	4.70	1.70	2925	4050
R = (m/h) = ELEVATION SPEED OF CASTING H = (m) = TOTAL CASTING HEIGHT Hm = (m) = DEPTH OF MAX. PRESSURE Pm = (daN/m ²) = MAX. PRESSURE Pf = (daN/m ²) = PRESSURE AT THE BOTTOM t = (°C) = AMBIENT TEMPERATURE CN = NORMAL CONCRETE CV = VIBRATED CONCRETE $Pf = \frac{3R - (H-Hm)}{3R} \times Pm$ 						1.75	3025	4150
						1.80	3100	4275
						1.85	3200	4400
						1.90	3275	4500
						1.95	3350	4625
						2.00	3400	4750
						2.05	3500	4900
						2.10	3600	5000
						2.15	3700	5100
						2.20	3800	5225
						2.25	3900	5350
						2.30	3975	5475
						2.35	4050	5600
						2.40	4125	5700
						2.45	4225	5850
						2.50	4300	5950
						2.55	4400	6075
						2.60	4500	6200
						2.65	4575	6300
						2.70	4650	6400
						2.75	4725	6500
						2.80	4800	6600
						2.85	4900	6750
						2.90	4975	6850
						2.95	5075	7000
						3.00	5125	7100
						3.10	5300	7400
						3.20	5500	7600
						3.30	5675	7800
						3.40	5800	8075
						3.50	6000	8300
						3.60	6200	8500
						3.70	6400	8800
						3.80	6550	9000
						3.90	6700	9250
						4.00	6875	9500
						4.20	7200	10000
						4.40	7550	10500
						4.60	7900	11000

IN ORDER TO USE THE TABLE, CHOOSE THE (Pm) OF THE CONCRETE ON THE FORMWORK UNDER COLUMN (CN) OR (CV). THE VALUE (Hm) IS SHOWN ON THE SAME LINE. THE VALUE OF (R) IS THEN FOUND ALONGSIDE BOX (X) WHICH SHOWS THE VALUES OF (t) AND (Hm).

EXAMPLE:
CONSIDERING A (CV) CON (Pm) ON THE FORMWORK OF 3550 kg/m², THE (Hm) VALUE CORRESPONDS TO 1.5 m. WITH (t) = 15°C AND (Hm) = 1.5 m. THE VALUE OF R = 0.5 m/h

	Pm (daN/m ²)
MAGNUM	6000
P300	6000
MINIMAG	6000
DURA-CLAMP	6000

*

DURA-CLAMP MODULAR FORMWORK	
t (°C)	R (m/h)
5°C ----->	0.9 m/h
10°C ----->	1.5 m/h
15°C ----->	2.0 m/h
20°C ----->	2.8 m/h
25°C ----->	3.7 m/h



PILOSIO
BUILT TO BUILD

US Corporate Headquarters

UNISPAN USA
600 Seasons Rd
Stow, Ohio 44224
Phone: 330.247.1618
FAX: 330.752.4950

FLORIDA BRANCH

UNISPAN
8470 Belvedere rd.
West Palm Beach, FL. 33409
Phone: 561.513.6737
FAX: 561.513.6727